
Engineering A Clean Energy Policy

Kristina M. Johnson, PhD McGill University May 28, 2014





Aspirational Goals: Cut CO₂ Emissions 80% and Petroleum-based Energy Use 75% by 2050



Strategic Technology Energy Plan (STEP) Objective:

Describe a technical path to meet US energy & environment goals

STEP engineered with several design criteria in mind:

- A portfolio approach
- Focus on known technologies Low Risk
- Long-term view
- No economic or carbon sink offsets

Evaluate the direct costs and benefits relative to BAU

Costs and benefits "in-scope":

- Direct capital, operating and fuel expense between 2010 and 2050
- The "residual value" of newer assets and lower ongoing costs after 2050
- All calculated on "societal" basis
 - No intent to describe how costs and benefits could be split between sectors

Costs and benefits "out-of-scope":

- Benefits to national security
- Domestic job creation and global trade
- Impact on health

STEP developed by DOE program offices – BCG worked with Under Secretary's team to refine plan, evaluate cost and edit report


STEP built around five key levers

Five key levers

- 1. Decarbonize electrical generation
- 2. Switch from fossil fuels to electricity for heating and personal transportation.
- 3. Increase energy efficiency and conservation.
- 4. Modernize transmission and distribution.
- 5. Substituting biofuels for petroleum in freight transportation.

Description


- 1. Balance of Renewable, Fossil and Nuclear Energy.
- 2. Electrify LDV transport 50% penetration by 2035.
- 3. 23 Quad reduction by 2050.
- 4. Supply and demand side mgt.
- 5. Focus biomass resources on HDV and air transportation for freight.




IT Innovation Scales Much Faster Than Energy



SALES OF PERSONAL AUDIO/VIDEO MEMORY SINCE 2000









Collective Action Is Crucial

















Wind power installed capacity grew 49% from 2010 to 2012

Year	MW	Total
2010	5,404	40,267
2011	6,649	46,916
2012	13,091	60,007
2013*	2,398	62,405



US Photovoltaic installed capacity grew 208% from 2010 to 2012

Year	Additional MW	Total
2010	850	2,534
2011	1,915	4,449
2012	3,364	7,813
2013*	4,400	12,219




MW Installed Capacity Growth in the US Compared to Electricity Usage

	2010	2011	2012	Change	% Growth
Wind (in MW)	40,267	46,916	60,007	19,740	49%
Solar (in MW)	2,534	4,449	7,813	5,279	208%
Hydro (in MW)*	78,825	78,652	*78,652	~2%	*0%

Electricity Usage (in					
pwh - 10 ¹⁵)	3.886 pwh	3.883 pwh	3.823 pwh	.063pwh	-1.60%








Automated Demand Response




Electric load profile for PG&E participants on 8/30/2007



Peak Reduction is Paramount



Hourly Loads as Fraction of Peak, Sorted from Highest to Lowest



>25% of distribution and > 10% of generation assets are needed less than 5% of the time
>(\$100's of bns of investments)







Key findings of STEP

Technical feasibility

- 1. STEP is technologically feasible, but requires pulling ALL available levers.
- 2. Biomass for liquid fuel the critical area where STEP requires a "stretch".
 - Biomass-based fuel required to carbonize heavy duty vehicle fleet (e.g., work trucks, planes)
 - Biomass not used in passenger vehicle fleet – must be electrified
- 3. Long-term focus makes some short term options less attractive
 - Most significantly, replacing coal with natural gas for power generation
 - Sufficient to meet 2030 target, but requires CCS retrofit to achieve 2050 target
- 4. Decarbonization a more "concrete" emissions solution than efficiency

Evaluation of costs

- 1. STEP is roughly breakeven on a present value basis versus BAU over 2010-2050.
 - However, upfront investment drives
 ~\$1T trough and takes ~25 years to
 reach cash flow breakeven
- 2. STEP puts the country in a much better position looking forward from 2050 than does BAU.
 - STEP "residual value" is very significant (>\$600B) even in present value terms
- 3. Costs and benefits do not accrue evenly across sectors.
 - Critical to have a cohesive plan across sectors to address imbalances
 - Must execute across all sectors to achieve goal


STEP total cost minus BAU, in aggregate

Cash flow savings of STEP compared to BAU

Present value of STEP savings compared to BAU


Cumulative Cash Cost (\$B, 2009)

Discounted Cost (\$B, 2009)



Or, We Could Keep Doing This:





HYDROPOWER DEVELOPMENT STATISTICS



Overview of US Hydropower Fleet

Analysis of Federal Hydro Power Fleet

<u>Organization</u>	<u>Total</u> <u>Capacity (MW)</u>	Percentage of Federal Fleet	<u>Percentage of</u> <u>US Fleet</u>
USACE	20,500	50%	22%
USBR	14,800	36%	16%
TVA	5,500	13%	6%
Total Federal	40,800	100%	43%
Total US	95,100		



Federal Government: Potential Hydropower Increases

Hydropower Potential at Federal Facilities

<u>Type</u>	Capacity (MW)	Generation (MWh)	Potential Capacity Increase to Current Federal Hydro Fleet	Potential Generation Increase to Current Federal Hydro Fleet	US Homes Powered Annually by Improvements
USACE Improvements	12,998	45,944,463	32%	38%	4,073,091
USBR Improvements	268	1,168,248	1%	1%	103,568
Total Improvements	13,266	47,112,711	33%	39%	4,176,659
Total Current Federal Hydropower Fleet	40,800	121,200,000			10,744,681
Current Federal Fleet + Improvements	54,066	168,312,711			14,921,340


Overview of Federal Hydro Fleet

Quantity and Size of Federal and Private Hydropower Fleets

<u>Organization</u>	Number of Projects	Number of Units	Total Capacity (MW)	Average Project Size (MW)	Average Units per Project	Average Unit Size (MW)
USACE	75	353	20,500	276	5	58
USBR	58	194	14,800	255	3	76
TVA	30	113	5,500	183	4	49
Total Federal	163	660	40,800	251	4	62
FERC Licenses	1012	-	53,500	53	-	-
FERC Exemptions	595	-	800	1	-	-
Total Private	1607	-	54,300	34	-	-

USACE Overview (continued)

		# of	Capacity
		Plants	(MW)
	Portland	12	5,531
NW	Walla Walla	6	-,
15,714	Seattle	3	3,023
MW	Omaha	6	2,530
	Kansas City	2	207
	Mobile	8	-,
SA	Savannah	3	,
2,864	Wilmington	2	
MW	Charleston	1	84
	Atlanta		
	Jacksonville		
	Little Rock	7	,
SW	Tulsa	8	
1,763	Ft. Worth	3	90
MW	Dallas		
	Galveston		
	Nashville	8	-
	Detroit	1	18
GL&O	Buffalo		
945	Cincinnati		
MW	Huntington		
	Louisville		
	Pittsburgh		
		 	
	Vicksburg	3	
MVa	St. Louis	1	58
227	Memphis		
MW	St. Paul		
	New Orleans		
	Rock Island		



*No hydropower plants located in the South Pacific and North Atlantic divisions *Additional opportunity - USACE unpowered dams

U.S. Army Corps of Engineers: Potential Hydropower Increases


Hvdro	power Potential at USACE Facilities
,	

Improvement <u>Type</u>	Capacity (MW)	Generation (MWh)	Capacity Increase to Current USACE Hydro Fleet	Generation Increase to Current USACE Hydro Fleet	US Homes Powered Annually by Improvements**
Capacity Expansion at Existing Hydro Facilities*	3,503	10,543,477	17%	17%	934,705
Development of New Hydro at Existing Dams	8,353	31,963,845	41%	52%	2,833,674
Rehabilitation of Existing Hydro Facilities*	1,142	3,437,141	6%	6%	304,711
Total Improvements	12,998	45,944,463	63%	74%	4,073,091

Sources

- Bureau of Reclamation. U.S. Department of the Interior.
 Hydropower Resource Assessment at Existing Reclamation
 Facilities. Power Resources Office, 2011.
- Office of Energy Efficiency and Renewable Energy. U.S. Department of Energy. An Assessment of Energy Potential at Non-Powered Dams in the United States. Idaho Operations Office, 2012.
- U.S. Army Corps of Engineers. U.S. Department of the Army.
 Outlook for the U.S. Army Corps of Engineers Hydropower
 Program. Institute for Water Resources, 2011
- U.S. Department of the Interior, U.S. Department of the Army,
 U.S. Department of Energy. Potential Hydroelectric
 Development at Existing Federal Facilities. 2007.

Mahoning Creek Hydroelectric Project: 6.5 MW and 22,000 MWh Western PA



ENDURING HYDRO



Draft tubes (Discharge) set in place in powerhouse end of May



Spiral cases welded to conical draft tube. Small Turbine Shutoff Valve installed on concrete support.



Uncovering the conduit in Monolith 15 on the downstream face of the dam.



Valve vault base slab pour on 07/31/2013



By the end of September there were 15 pieces of penstock pipe installed.

Photos of MCHC progress

Installation of both spiral cases and TSV's in powerhouse




Installation of concrete lagging for soldier pile wall



Pouring Valve Vault Base Slab





Sole plate and lower bracket installed in powerhouse last week of September. Generator installation in October. Dry commissioning November 2013

Major Q4 Milestones

Finance

Convert construction loan to permanent loan. PPA in place.

Technical

Installation of Roller Gate and intake sub-frame on August 15, 2013

Complete walls of powerhouse on September 9, 2013

Finish turbine and generator installation on October 11, 2013

Complete build of penstock and TSV's on October 12, 2013

Install interconnections on October 15, 2013

Commission turbine and generator on December 4, 2013

Impact

Equivalent to planting 1,000,000 fully grown trees or taking 4,000 cars off the road.

30X more efficient than "Cash for Clunkers"













Its all our responsibility

